

as you will be cutting a significant quadrant of the tree out by their removal. The tree v able to grow in that quadrant once these limbs are removed.

With no maintenance having occurred on this tree at all and thus has been allowed completely out of shape, it is also full with a substantial amount of dead wood. As with th tree there has been an incredible amount of growth between the line of all the oak tree; of concern is that the limbs that have been damaged are supporting a very significant ; growth from the creepers and removal of these limbs will allow a huge amount of growth Bound Lane and that the remaining growth will be unable to support its weight, on this b; it is recommended to remove all the self-seeded trees and shrubs between the 3 off Oak

On closer inspection it is clear also that this area has been used a dumping ground n; green waste etc and has now resulted in a bank of unstable ground between the oak tr; also is seen to contain much rubbish inclusive of tins, bottles and disturbingly drug par; Just this alone is sufficient to make Log Off Tree Surgeons extremely cautious when ; the clearance activity.

### Task 3

Stump grind resultant tap roots created from Tasks 1 and 2, also stump grind tap; shrubbery growth and self-seeded trees. Please note this will still leave you with a mou; higher than Bound Lane and will need to be levelled and disposed of formally as this wil; either mixed and non green waste.

### Task 4

The remaining Oak tree is in fair condition but desperately needs to be reduced all over; dead wooded as some of the dead limbs again represent risk to the traffic and ; transiting Bound Lane. Where this trees lower limbs protrude in a South Westerly direct; in danger of breaching your neighbours roof and or allow birds to stand directly on the; the cars driveway, these should be removed entirely or at least cut substantially back; clear of the neighbours car and roof for many years.

### Costings:

Task 1	£[REDACTED] (4 Man team)
Task 2	£[REDACTED] (4 Man team)
Task 3	£[REDACTED]
Task 4	£[REDACTED] (3 man team)

Price includes clearance of all core wood but with the caveats of potential add; described in email dated 28<sup>th</sup> December 2016.

Submitted for your consideration

Kind regards